

Job Filename: AUTOZONE  
Job Description: Untitled

Scale: 1":19.95'

Cross-section spacing: 0.50 FT

Soil Expansion: 0%  
Soil Compression: 35%  
Import Soil Compression: 35%

Cut Area: 2757.5 FT2  
Fill Area: 47743.5 FT2  
Work Area: 50647.3 FT2

Bank Cut: 21.8 YD3  
Expanded Cut: 21.8 YD3  
Bank Fill: 3568.0 YD3  
Topsoil Stripped: 618.6 YD3  
Topsoil Replaced: 0.0 YD3

Import: 4795.1 YD3  
Topsoil Export: 618.6 YD3

Job Filename: AUTOZONE

Job Description: Untitled

Please note that the following information is based solely on the areas' shape and depth and without regard to Perimeters and Excluded Areas.

Area Name	Area, FT2	Perimeter, FT
BLDG	7044.0	351.2

Subgrade Name	Area, FT2	Perimeter, FT	Volume, YD3
PAVING	14103.0	1082.0	413.5
PAVING	363.7	147.0	10.7
CONCRETE PAVING	148.0	59.1	2.7
CONCRETE PAVING	248.5	81.9	4.6
CONCRETE PAVING	1158.3	170.6	21.5
SIDEWALK	7222.2	1606.0	178.3
SIDEWALK	150.7	83.3	3.7
BLDG	7044.0	351.2	130.4

Topsoil Area, Stripped	Area, FT2	Perimeter, FT	Volume, YD3
TOPSOIL	50641.5	936.6	625.2

Job Filename: AUTOZONE

Job Description: Untitled

Please note that the following information is based solely on the areas' shape and depth and without regard to Perimeters and Excluded Areas.

PAVING - None

SURFACE	1.50 in	65.3 YD3	0.00 TON
LIMEROCK	8.00 in	348.2 YD3	0.00 TON

PAVING - None

SURFACE	1.50 in	1.7 YD3	0.00 TON
LIMEROCK	8.00 in	9.0 YD3	0.00 TON

CONCRETE PAVING - None

CONCRETE PAVING	6.00 in	2.7 YD3	0.00 TON
-----------------	---------	---------	----------

CONCRETE PAVING - None

CONCRETE PAVING	6.00 in	4.6 YD3	0.00 TON
-----------------	---------	---------	----------

CONCRETE PAVING - None

CONCRETE PAVING	6.00 in	21.5 YD3	0.00 TON
-----------------	---------	----------	----------

SIDEWALK - None

SIDEWALK	4.00 in	89.2 YD3	0.00 TON
ROCK	4.00 in	89.2 YD3	0.00 TON

SIDEWALK - None

SIDEWALK	4.00 in	1.9 YD3	0.00 TON
ROCK	4.00 in	1.9 YD3	0.00 TON

BLDG - None

BLDG	6.00 in	130.4 YD3	0.00 TON
------	---------	-----------	----------

Job Filename: AUTOZONE

Job Description: Untitled

Please note that the following information is based solely on the areas' shape and depth and without regard to Perimeters and Excluded Areas.

SURFACE	67.0 YD3	0.00 TON
LIMEROCK	357.2 YD3	0.00 TON
CONCRETE PAVING	28.8 YD3	0.00 TON
SIDEWALK	91.0 YD3	0.00 TON
ROCK	91.0 YD3	0.00 TON
BLDG	130.4 YD3	0.00 TON