

Job Filename: DQ
Job Description: Untitled

Scale: 1":29.85'

Cross-section spacing: 0.50 FT

Soil Expansion: 0%
Soil Compression: 20%
Import Soil Compression: 20%

Cut Area: 12898.0 FT2
Fill Area: 49357.8 FT2
Work Area: 62479.0 FT2

Bank Cut: 325.5 YD3
Expanded Cut: 325.5 YD3
Bank Fill: 3112.2 YD3
Topsoil Stripped: 1156.1 YD3
Topsoil Replaced: 639.9 YD3

Import: 3409.1 YD3
Topsoil Export: 516.2 YD3

EarthWorks Elements, Dimensions Report
 Job Filename: DQ
 Job Description: Untitled

Date: 03/14/21 Time: 06:33 PM

Please note that the following information is based solely on the areas' shape and depth and without regard to Perimeters and Excluded Areas.

Area Name	Area, FT2	Perimeter, FT
BLDG	2337.3	211.6
Subtotal for Group: 15	2337.3	211.6

Subgrade Name	Area, FT2	Perimeter, FT	Volume, YD3
PARKING LOT	21871.9	1511.0	607.6
Subtotal for Group: 1	21871.9	1511.0	607.6
CONCRETE PAVING	1699.8	315.4	63.0
CONCRETE PAVING	343.3	74.1	12.7
Subtotal for Group: 3	2043.1	389.6	75.7
SIDEWALK	44.0	30.1	1.1
SIDEWALK	1531.5	433.6	37.8
SIDEWALK	50.4	31.4	1.2
Subtotal for Group: 5	1625.9	495.0	40.1
BLDG	2337.3	211.6	72.1
Subtotal for Group: 15	2337.3	211.6	72.1

Topsoil Area, Stripped	Area, FT2	Perimeter, FT	Volume, YD3
TOPSOIL	62478.6	996.6	1157.0

Please note that the following information is based solely on the areas' shape and depth and without regard to Perimeters and Excluded Areas.

PARKING LOT - None			
SURFACE	1.00 in	67.5 YD3	0.00 TON
INTER	2.00 in	135.0 YD3	0.00 TON
AGG	6.00 in	405.0 YD3	0.00 TON
CONCRETE PAVING - None			
PCC	6.00 in	6.4 YD3	0.00 TON
AGG	6.00 in	6.4 YD3	0.00 TON
CONCRETE PAVING - None			
PCC	6.00 in	31.5 YD3	0.00 TON
AGG	6.00 in	31.5 YD3	0.00 TON
SIDEWALK - None			
SIDEWALK	4.00 in	0.6 YD3	0.00 TON
AGG	4.00 in	0.6 YD3	0.00 TON
SIDEWALK - None			
SIDEWALK	4.00 in	0.5 YD3	0.00 TON
AGG	4.00 in	0.5 YD3	0.00 TON
SIDEWALK - None			
SIDEWALK	4.00 in	18.9 YD3	0.00 TON
AGG	4.00 in	18.9 YD3	0.00 TON
BLDG - None			
BLDG	4.00 in	28.9 YD3	0.00 TON
GRANULAR	6.00 in	43.3 YD3	0.00 TON

EarthWorks Elements, Materials Summary Report Date: 03/14/21 Time: 06:33 PM
Job Filename: DQ
Job Description: Untitled

Please note that the following information is based solely on the areas' shape and depth and without regard to Perimeters and Excluded Areas.

Material totals in group 1

AGG	405.0 YD3	0.00 TON
INTER	135.0 YD3	0.00 TON
SURFACE	67.5 YD3	0.00 TON

Material totals in group 3

AGG	37.8 YD3	0.00 TON
PCC	37.8 YD3	0.00 TON

Material totals in group 5

AGG	20.1 YD3	0.00 TON
SIDEWALK	20.1 YD3	0.00 TON

Material totals in group 15

BLDG	28.9 YD3	0.00 TON
GRANULAR	43.3 YD3	0.00 TON

Material totals by name

AGG	462.9 YD3	0.00 TON
BLDG	28.9 YD3	0.00 TON
GRANULAR	43.3 YD3	0.00 TON
INTER	135.0 YD3	0.00 TON
PCC	37.8 YD3	0.00 TON
SIDEWALK	20.1 YD3	0.00 TON
SURFACE	67.5 YD3	0.00 TON