



Takeoff By Location

Addendum 1 Discount Tire - Thornton

Disclaimer: The recipient acknowledges that the take-off(s) is an estimate based solely on information provided. The recipient is responsible for reviewing the take-off provided for accuracy and accepts all responsibility for determining the necessary supply of materials needed to bid and or complete the building project. Total Takeoffs makes NO guarantee as to the accuracy of the estimate. Total Takeoffs is NOT be responsible for any claims, disputes or liability arising from the accuracy of take-off(s) provided. All questions pertaining to the takeoff reports, must be asked within 30 days from receiving the takeoff reports.

Notes

Takeoff

Roof Penetrations

Name	Color	Qty	Units
30" x 30" Exhaust Fan		2.00	EA
30" x 36" Roof Access Hatch		1.00	EA
4' x 6' Metal Framed Skylight		7.00	EA
6" Roof drain and overflow		4.00	EA
Roof exhaust fan Duct		1.00	EA

Roof Vents



Name	Color	Qty	Units
3" VTR		2.00	EA
4" VTR		2.00	EA












Generated by Total Takeoffs

Page 1 of 2

Takeoff

Roofing Materials

Name	Color	Qty	Units
18 GA Sheet Metal Sump Pan		8.38	SQ FT
2" Damp collar		2.00	EA
2'2" Parapet Cap		271.12	FT
3'2" Parapet Cap		89.92	FT
4" Continuous cant		378.76	FT
4'9" Parapet Cap		34.94	FT
6" TPO cover Tape		395.18	FT
Aluminum Spun Base		2.00	EA
Aluminum Spun Base		2.00	EA
Cant Strip		232.31	FT

Counter Flashing		234.95	FT
Counterflashing		10.93	FT
Flashing		233.26	FT
Flexible sealant		395.18	FT
Prefab molded pipe flashing		1.00	EA
Prefab molded pipe flashing		2.00	EA
Prefab molded pipe flashing		2.00	EA
Roof Cricket		729.36	SQ FT
Stepped PVC Boot w/ adjustable stainless steel clamps		2.00	EA
Stepped PVC Boot w/ adjustable stainless steel clamps		2.00	EA
Surface Textured Walkway Pads		266.42	SQ FT

TPO Roofing

Name	Color	Qty	Units
60 mil Class "C" Fully Adhered TPO		10,684.20	SQ FT
Rigid 6" Min R-30 Polyisocyanurate Insulation		7,692.23	SQ FT