



Materials By Location

10% Waste Added

www.totaltakeoffs.com
813-478-5568

Express Oil Change

Disclaimer: The recipient acknowledges that the take-off(s) is an estimate based solely on information provided. The recipient is responsible for reviewing the take-off provided for accuracy and accepts all responsibility for determining the necessary supply of materials needed to bid and or complete the building project. Total Takeoffs makes NO guarantee as to the accuracy of the estimate. Total Takeoffs is NOT be responsible for any claims, disputes or liability arising from the accuracy of take-off(s) provided. All questions pertaining to the takeoff reports, must be asked within 30 days from receiving the takeoff reports.

Notes

100 - Concrete

100 - Footings

Name	Description	Qty	Units
#4 Rebar 1' x 4' Pre- Bent	Vertical Dowels	167	EA
#4 Rebar x 20'	Horizontal	52	EA
#4 Rebar x 3'	Horizontal	120	EA
#4 Rebar x 3'	Transverse	167	EA
Concrete, 3000 PSI	Footings	26	CU YD
Rebar Chairs - Single		253	EA

105 - Level 1 Slabs

Name	Description	Qty	Units
#3 26" x 20" Stirrup	12" OC	227	EA
#4 Rebar 2' x 4' Pre- Bent	Vertical Dowels	33	EA
#4 Rebar x 1.5'	Transverse	33	EA
#4 Rebar x 2'	Horizontal	66	EA

Generated by Total Takeoffs

100 - Concrete

105 - Level 1 Slabs

Name	Description	Qty	Units
#4 Rebar x 20'	Horizontal	13	EA
#6 Rebar 1' x 5' Pre- Bent	Vertical Dowels	57	EA
#6 Rebar x 20'	Horizontal	58	EA
1/2" Anchor Bolts		32	EA
1/2" x 6" Headed Studs		44	EA
6" x 1/2" x 6" Plate		11	EA
2" x 2" x 1/2" W.C.		25	EA

6"x6" WWM W2.9 x W2.9	7.5' x 20' Sheets, 150 SQ FT coverage	35	Sheet(s)
Concrete, 3000 PSI	Footings	3	CU YD
Concrete, 3000 PSI	Mono Footings	3	CU YD
Concrete, 3000 PSI	Slabs	114	CU YD
Mesh Chairs	1 Per Every 4 SQ FT	1197	EA
Rebar Chairs - Double		58	EA
Rebar Chairs - Single		17	EA
Rebar Chairs - Triple		17	EA
Vapor Barrier 20' x 100' roll	High Performance Polyethylene	2	Roll(s)
Vapor Barrier Tape	Per Roll	1	Roll(s)

135 - CIP Walls

Name	Description	Qty	Units
#4 Rebar x 20'	Horizontal	162	EA
#4 Rebar x 8'	Vertical	322	EA
Concrete, 3000 PSI	Walls	40	CU YD

137 - Site Concrete

Name	Description	Qty	Units
#4 Rebar 1' x 4' Pre- Bent	Vertical Dowels	17	EA
#4 Rebar x 20'	Horizontal	6	EA
24" x 5' Detectable Warning Cast-In-Place Mat		2	EA
Concrete, 3000 PSI	Bollards	7	CU YD
Concrete, 3000 PSI	Footings	44	CU YD
Concrete, 3000 PSI	Mono Footings	3	CU YD
Concrete, 3000 PSI	Slabs	30	CU YD
Concrete, 4000 PSI	Slabs	3	CU YD

Generated by Total Takeoffs

Page 2 of 3

100 - Concrete

137 - Site Concrete

Name	Description	Qty	Units
Rebar Chairs - Double		9	EA
Rebar Chairs - Single		3	EA

151 - 5" Oil Pit Slab

Name	Description	Qty	Units
6"x6" WWM W2.9 x W2.9	7.5' x 20' Sheets, 150 SQ FT coverage	9	Sheet(s)
Concrete, 3000 PSI	Slabs	21	CU YD
Mesh Chairs	1 Per Every 4 SQ FT	319	EA
Vapor Barrier 20' x 100' roll	High Performance Polyethylene	1	Roll(s)
Vapor Barrier Tape	Per Roll	1	Roll(s)

152 - 12" Oil Pit Slab

Name	Description	Qty	Units
#5 Rebar x 20'	Horizontal	158	EA
Concrete, 3000 PSI	Slabs	50	CU YD
Rebar Chairs - Single	1 Per Every 4 SQ FT	638	EA
Vapor Barrier 20' x 100' roll	High Performance Polyethylene	1	Roll(s)
Vapor Barrier Tape	Per Roll	1	Roll(s)

Generated by Total Takeoffs

Page 3 of 3