



Takeoff By Location

www.totaltakeoffs.com
813-478-5568

Express Oil Change

Disclaimer: The recipient acknowledges that the take-off(s) is an estimate based solely on information provided. The recipient is responsible for reviewing the take-off provided for accuracy and accepts all responsibility for determining the necessary supply of materials needed to bid and or complete the building project. Total Takeoffs makes NO guarantee as to the accuracy of the estimate. Total Takeoffs is NOT be responsible for any claims, disputes or liability arising from the accuracy of take-off (s) provided. All questions pertaining to the takeoff reports, must be asked within 30 days from receiving the takeoff reports.

Notes

Takeoff

100 - Footings

Name	Color	Qty	Units
2' x 2' x 1'd pads w/ (3)#4 ea way	[Red]	18.00	EA
3'8"w x 1'd footings w/ (5)#4 cont, #4 trans 12"oc, #4 dowels 1' x 5'	[Teal]	150.94	FT

105 - Level 1 Slabs

Name	Color	Qty	Units
18"w x 7"d mono footing w/ (3)#4 cont, #4 trans 24oc	[Olive]	59.34	FT
3" slab, W2.9	[Light Green]	1,129.95	SQ FT
30" x 30" x 12"d mono pads w/ (3)#4 ea way	[Dark Red]	10.00	EA
5" slab on grade w/ W2.9	[Light Blue]	3,425.18	SQ FT
6" x 1/2" x 6" plate & (4) 1/2" x 6" headed studs 36"oc, #4 dowels 2' x 4' 12"oc, 1/2" AB 48oc	[Dark Blue]	29.40	FT
Mono footing 0.37 sf	[Teal]	28.99	FT
Mono footing 12 area	[Magenta]	5.26	SQ FT

Generated by Total Takeoffs

Page 1 of 3

Takeoff

105 - Level 1 Slabs

Name	Color	Qty	Units
Mono footing 5.1 sq ft w/ (4)#6 cont, #3 ties 12"oc, #6 dowels 1' x 5' 48"oc	[Cyan]	142.45	FT
Mono footing 5.3 sq ft w/ (4)#6 cont, #3 ties 12"oc, #6 dowels 1' x 5' 48"oc	[Yellow]	62.92	FT
Mono footing 8 area	[Blue]	5.08	SQ FT
S5.1/4 thickened edge area	[Purple]	0.37	SQ FT

135 - CIP Walls

Name	Color	Qty	Units
10" x 8" CIP walls w/ (2)#4 vert 12"oc, (2)#4 horiz 12"oc	[Green]	146.01	FT

137 - Site Concrete

Name	Color	Qty	Units
1 s.f. curb & gutter	[Green]	781.31	FT
1'6" dia x 3'2" bollard footings	[Magenta]	26.00	EA
1'w x 4'd apron thickened edge	[Dark Red]	191.98	FT
1.2 sf dumpster mono footing w/ (2)#4 cont, #4 dowels 1' x 4' 24oc	[Olive]	29.35	FT
1.6 s.f. curb & gutter	[Magenta]	176.05	FT
2'6" curb & gutter section area	[Blue]	1.62	SQ FT
4" concrete apron	[Teal]	958.86	SQ FT
4" concrete sidewalks/ramps	[Yellow]	1,104.54	SQ FT
6" 4000 dumpster slab	[Light Yellow]	112.77	SQ FT
6" dia x 3'6" conc fill for bollards	[Cyan]	26.00	EA
8" w x 4" d dumpster mono footing w/ (1)#4 cont	[Dark Blue]	9.36	FT
Dumpster footing area	[Green]	1.20	SQ FT

151 - 5" Oil Pit Slab

Name	Color	Qty	Units
5" slab w/ W2.9 x W2.9	[Yellow]	1,213.35	SQ FT

152 - 12" Oil Pit Slab

Name	Color	Qty	Units
12" slab w/ (2) #5 rebar mats 24oc	[Yellow]	1,213.35	SQ FT

Generated by Total Takeoffs

Page 2 of 3

Takeoff

Generated by Total Takeoffs

Page 3 of 3