

Job Filename: HYAT WACO EW  
Job Description: Untitled

Scale: 1":30'

Cross-section spacing: 0.50 FT

Soil Expansion: 0%  
Soil Compression: 0%  
Import Soil Compression: 0%

Cut Area: 52056.5 FT2  
Fill Area: 34978.8 FT2  
Work Area: 88232.5 FT2

Bank Cut: 1847.1 YD3  
Expanded Cut: 1847.1 YD3  
Bank Fill: 1651.7 YD3  
Topsoil Stripped: 1623.9 YD3  
Topsoil Replaced: 452.0 YD3

Export: 195.4 YD3  
Topsoil Export: 1171.9 YD3

Job Filename: HYAT WACO EW

Job Description: Untitled

Please note that the following information is based solely on the areas' shape and depth and without regard to Perimeters and Excluded Areas.

Area Name	Area, FT2	Perimeter, FT
BLDG	13325.7	580.3

Subgrade Name	Area, FT2	Perimeter, FT	Volume, YD3
PAVING	43656.4	2504.8	808.5
SIDEWALK	1917.6	675.0	23.7
DUMPSTER PAD	354.9	78.6	8.8
SIDEWALK	4093.1	1635.5	50.5
BLDG	13325.7	580.3	205.6

Topsoil Area, Stripped	Area, FT2	Perimeter, FT	Volume, YD3
TOPSOIL	88232.5	1195.4	1633.9

Job Filename: HYAT WACO EW

Job Description: Untitled

Please note that the following information is based solely on the areas' shape and depth and without regard to Perimeters and Excluded Areas.

PAVING - None			
CONCRETE	6.00 in	808.5 YD3	0.00 TON
SIDEWALK - None			
CONCRETE	4.00 in	23.7 YD3	0.00 TON
DUMPSTER PAD - None			
CONCRETE	8.00 in	8.8 YD3	0.00 TON
SIDEWALK - None			
CONCRETE	4.00 in	50.5 YD3	0.00 TON
BLDG - None			
BLDG SLAB	5.00 in	205.6 YD3	0.00 TON

Job Filename: HYAT WACO EW

Job Description: Untitled

Please note that the following information is based solely on the areas' shape and depth and without regard to Perimeters and Excluded Areas.

CONCRETE	891.4 YD3	0.00 TON
BLDG SLAB	205.6 YD3	0.00 TON