

Description	Qty	Units	Color	Price	Extended
<b>CLEARING AND SITE PREPARATION</b>					
SAWCUT	261	FT	Blue	\$	-
CURB T.B.R.	268	FT	Cyan	\$	-
ASPHALT PAVING T.B.R.	403	SQ FT	Magenta	\$	-
HYDRANT T.B.R.	1	EA	Red	\$	-
<b>SOIL EROSION &amp; SEDIMENT CONTROL</b>				\$	-
SILT FENCE	523	FT	Green	\$	-
INLET PROTECTION	7	EA	Blue	\$	-
CONSTRUCTION ENTRANCE	512	SQ FT	Yellow	\$	-
<b>EARTHWORK</b>				\$	-
TOPSOIL STRIP 6" THK.	1,623	CY		\$	-
BANK CUT	1,847	CY		\$	-
BANK FILL	1,651	CY		\$	-
EXPORT	195	CY		\$	-
ROUGH GRADE SITE	88,232	SF		\$	-
TOPSOIL REPLACED 6" THK.	452	CY		\$	-
TOPSOIL EXPORT	1,171	CY		\$	-
<b>SANITARY SEWER</b>				\$	-
CONNECT TO EX. SANITARY LINE	1	EA	Olive	\$	-
8" SANITARY	90	FT	Dark Blue	\$	-
CLEANOUT	3	EA	Purple	\$	-
<b>STORM SEWER</b>				\$	-
5' CURB INLET, 0-8' DP.	3	EA	Teal	\$	-
WYE INLET, 0-8' DP.	1	EA	Red	\$	-
2'X2' GRATE INLET, 0-8' DP.	3	EA	Green	\$	-
3'X3' JUNCTION STRUCTURE	1	EA	Yellow	\$	-
18"X12" CONNECTION	3	EA	Magenta	\$	-
12" 45 DEG BEND	2	EA	Red	\$	-
18" 45 DEG BEND	3	EA	Green	\$	-
12" HDPE, 0-8' DP.	88	FT	Cyan	\$	-
18" RCP, 0-8' DP.	548	FT	Blue	\$	-
<b>WATER DISTRIBUTION</b>				\$	-
6" DIP FIRE SERVICE	140	FT	Green	\$	-
3" DOMESTIC SERVICE	130	FT	Dark Green	\$	-
6" 45 DEG BEND	3	EA	Teal	\$	-
6" 90 DEG BEND	1	EA	Dark Blue	\$	-
8"X6" REDUCER	1	EA	Purple	\$	-
6" DCVA VAULT	1	EA	Red	\$	-
10"X4" TEE	1	EA	Blue	\$	-
4"X3"	1	EA	Magenta	\$	-
3" 90 DEG .BEND	2	EA	Cyan	\$	-
3" METER VAULT	1	EA	Red	\$	-
8"X1" REDUCER	1	EA	Teal	\$	-
1" IRRIGATION METER BOX	1	EA	Red	\$	-
<b>CURB &amp; PAVEMENT</b>				\$	-
CONCRETE CURB & GUTTER	1,922	FT	Green	\$	-
CONCRETE SIDEWALK 4" THK.	6,397	SQ FT	Olive	\$	-
CONCRETE PAVEMENT 6" THK.	45,055	SQ FT	Dark Blue	\$	-
CONCRETE PAVING 8" THK.	753	SQ FT	Purple	\$	-
<b>No Waste Added</b>				\$	-