



Material Item Totals

NOTE:

105 - Framing				
Name	Qty	Units	Unit Price	Extended Price
(2) Layers 3/4" Struct Panel @ 4' Rough Treds	160	EA		\$ -
1 1/8" T&G OSB Subfloor	1,337	EA		\$ -
1" SLX Shaftliner Panel 2' x 10'	21	EA		\$ -
1" SLX Shaftliner Panel 2' x 12'	8	EA		\$ -
1/2" PT Plywood 4' x 8'	54	EA		\$ -
1/2" Thru Bolts	554	EA		\$ -
2 1/2" C-H @ 10' Stud	27	EA		\$ -
2 1/2" C-H @ 12' Stud	9	EA		\$ -
2 1/2" J @ 10' Bottom Track	8	EA		\$ -
2 1/2" J @ 10' Top Track	8	EA		\$ -
23/32" T&G OSB 4' x 8'	457	EA		\$ -
2x12 SYP #2 @ 12' Stringers	126	EA		\$ -
2x12 SYP #2 @ 14' Stringers	18	EA		\$ -
2x4 PT @ 16'	12	EA		\$ -
2x4 SYP #2 @ 10'	10	EA		\$ -
2x4 SYP #2 @ 12'	21	EA		\$ -
2x4 SYP #2 @ 12' stud	125	EA		\$ -
2x4 SYP #2 @ 16'	1,383	EA		\$ -
2x4 SYP #2 @ 8'	3	EA		\$ -
2x4 SYP #2 @ 8' stud	32	EA		\$ -
2x4 SYP #2 @ 9' stud	1,244	EA		\$ -
2x6 PT @ 16'	295	EA		\$ -
2x6 SYP #2 @ 10'	31	EA		\$ -
2x6 SYP #2 @ 10' stud	216	EA		\$ -
2x6 SYP #2 @ 12'	216	EA		\$ -
2x6 SYP #2 @ 12' stud	1,574	EA		\$ -
2x6 SYP #2 @ 16'	3,528	EA		\$ -
2x6 SYP #2 @ 8'	288	EA		\$ -
2x6 SYP #2 @ 8' stud	108	EA		\$ -
2x6 SYP #2 @ 9' stud	4,286	EA		\$ -
2x8 "HB" Joist Hangers	808	EA		\$ -
2x8 SYP #2 @ 12'	196	EA		\$ -
2x8 SYP #2 @ 16'	58	EA		\$ -
5 1/4 x 11 7/8	621	FT		\$ -
5 1/4 x 9 1/2	560	FT		\$ -
7/16" OSB 4' x 8'	1,042	EA		\$ -
A34 Clips	36	EA		\$ -
HU212-3	48	EA		\$ -
Shaftwall Clips	116	EA		\$ -
Subfloor Glue	670	EA		\$ -
Tyvek	33	Roll(s)		\$ -
Tyvek Tape	33	Roll(s)		\$ -
		Total :		\$ -
117 - Interior Doors				
Name	Qty	Units	Unit Price	Extended Price
005 LH	1	EA		\$ -
005 RH	1	EA		\$ -
006 RH	1	EA		\$ -
007 LH	1	EA		\$ -
008 LH	1	EA		\$ -
008-1 LH	1	EA		\$ -
009 LH	1	EA		\$ -

010 LH	1	EA	\$	-
011 RH	1	EA	\$	-
014 RH	1	EA	\$	-
015 LH	1	EA	\$	-
017 LH	1	EA	\$	-
018 LH	1	EA	\$	-
019 RH	1	EA	\$	-
020 RH	1	EA	\$	-
021 LH	1	EA	\$	-
022 LH	1	EA	\$	-
024-1 LH	1	EA	\$	-
029 RH	1	EA	\$	-
030 LH	1	EA	\$	-
031 RH	1	EA	\$	-
032 RH	1	EA	\$	-
033 RH	1	EA	\$	-
033-1 RH	1	EA	\$	-
034 RH	1	EA	\$	-
035 LH	1	EA	\$	-
041 LH	1	EA	\$	-
043 RH	1	EA	\$	-
044 LH	1	EA	\$	-
1A LH	4	EA	\$	-
231 RH	1	EA	\$	-
232 RH	1	EA	\$	-
234 LH	1	EA	\$	-
235 LH	1	EA	\$	-
2A RH	4	EA	\$	-
331 RH	1	EA	\$	-
332 RH	1	EA	\$	-
334 LH	1	EA	\$	-
335 LH	1	EA	\$	-
431 RH	1	EA	\$	-
432 RH	1	EA	\$	-
434 LH	1	EA	\$	-
435 LH	1	EA	\$	-
GR1 RH	75	EA	\$	-
GR2 LH	70	EA	\$	-
Pool Equip RH (No Tag)	1	EA	\$	-
Sliding Bath Door (Not in Schedule)	5	EA	\$	-
Total :			\$	-

125 - Insulation				
Name	Qty	Units	Unit Price	Extended Price
3 1/2" Sound Batt	20,432	SQ FT		\$ -
5 1/2" Sound Batt	47,680	SQ FT		\$ -
6 1/2" Batt Insulation	26,216	SQ FT		\$ -
Batt Insulation	558	SQ FT		\$ -
R-19 Insulation	22,349	SQ FT		\$ -
Total :			\$	-

130 - Drywall				
Name	Qty	Units	Unit Price	Extended Price
1/2" FR C Core Drywall 4' x 12'	26	EA		\$ -
1/2" Resilient Channels	19,138	FT		\$ -
5/8" Densarmour Plus 4' x 12'	66	EA		\$ -
5/8" Drywall 4' x 12'	1,427	EA		\$ -
5/8" FR C Core Drywall 4' x 12'	1,940	EA		\$ -
5/8" FR Drywall 4' x 12'	151	EA		\$ -
5/8" MR Drywall 4' x 12'	441	EA		\$ -
5/8" MR FR C Core Drywall 4' x 12'	295	EA		\$ -
Drywall Fasteners	16	EA		\$ -
Drywall Fasteners for Wood Studs	106	EA		\$ -
Joint Compound	468	EA		\$ -
Joint Tape	355	EA		\$ -
Resilient Channels	19,663	FT		\$ -
Total :			\$	-

132 - Acoustical Ceilings				
Name	Qty	Units	Unit Price	Extended Price
2x2 ACT ceilings	2,355	SQ FT		\$ -

2x4 ACT ceilings	460	SQ FT		\$ -
4x4 ACT ceilings	1,374	SQ FT		\$ -
Total :				\$ -

135 - Interior				
Name	Qty	Units	Unit Price	Extended Price
Pantry FRP (5' height)	447	SQ FT		\$ -
Window Casing	2,207	FT		\$ -
Total :				\$ -

139 - Flooring				
Name	Qty	Units	Unit Price	Extended Price
Carpet	26,599	SQ FT		\$ -
Carpet Base	7,907	FT		\$ -
Carpet Tile	1,260	SQ FT		\$ -
Tile	11,271	SQ FT		\$ -
Tile Base	5,856	FT		\$ -
Vinyl Base	985	FT		\$ -
Vinyl Tile	450	SQ FT		\$ -
Total :				\$ -
Sub				\$ -
Type tax % in next cell---->	0.07	Tax:		\$ -
Bid Total:				\$ -