



Consolidated List

Foundation Materials				
Name	Qty	Units	Unit Price	Extended Price
#5 Rebar 1' x 4'	65	EA		\$ -
#5 Rebar 2' x 2'	17	EA		\$ -
#5 Rebar x 20"	8	EA		\$ -
#5 Rebar x 20'	31	EA		\$ -
#5 Rebar x 26"	30	EA		\$ -
10 x 100 6 mil Black Plastic	3	EA		\$ -
3000 PSI Concrete	63	CU YD		\$ -
6"x6" 10/10 WWF 7.5' x 20' Sheets	18	EA		\$ -
Double Rebar Chairs	81	EA		\$ -
Footing Forms	875	SQ FT		\$ -
Slab Perimeter Forms	415	SQ FT		\$ -
Spread Footings Forms	46	SQ FT		\$ -
Wire Mesh Chairs	664	EA		\$ -
Total :				\$ -
Masonry Materials				
Name	Qty	Units	Unit Price	Extended Price
#3 Rebar x 20'	3	EA		\$ -
#4 Rebar x 20'	2	EA		\$ -
#5 Rebar 1' x 8'6" Pre-Bent	56	EA		\$ -
#5 Rebar 1' x 9' Pre-Bent	9	EA		\$ -
#5 Rebar x 20'	19	EA		\$ -
3000 PSI Grout	8	CU YD		\$ -
5" Door/Window Trim	119	FT		\$ -
7 5/8" Precast Sill x 3 ft 0 in	1	EA		\$ -
7 5/8" Precast Sill x 4 ft 0 in	4	EA		\$ -
7 5/8" Precast Sill x 5 ft 0 in	2	EA		\$ -
8" Precast Prestressed U Lintel x 17 ft 4 in	1	EA		\$ -
8" Precast U Lintel x 4 ft 6 in	7	EA		\$ -
8" Precast U Lintel x 4 ft 8 in	1	EA		\$ -
8" Precast U Lintel x 5 ft 10 in	2	EA		\$ -
8" Precast U Lintel x 7 ft 6 in	1	EA		\$ -

8" Precast U Lintel x 8 ft 0 in	1	EA		\$	-
8" x 12" x 12" Regular Block	29	EA		\$	-
8" x 8" x 16" Regular Block	1,419	EA		\$	-
8" x 8" x 16" Regular Open Lintel Block	162	EA		\$	-
9 Ga. Galvanized Ladder Wire	1,300	FT		\$	-
Cementitious Finish	1,341	SQ FT		\$	-
HETA-20	152	EA		\$	-
Lintel Screen	216	FT		\$	-
Mortar Sand	3	CU YD		\$	-
Type S Mortar 80# Bags	19	Bag(s)		\$	-

Total :				\$	-
---------	--	--	--	----	---

Header and Beams

Name	Qty	Units	Unit Price	Extended Price
Beam/Header Hanger As Needed	2	EA		\$ -
TBD per Engineer Beam/Header No Spec x 4'	1	EA		\$ -

Total :				\$	-
---------	--	--	--	----	---

Main Level Ceiling Joist

Name	Qty	Units	Unit Price	Extended Price
2x12 PT x 16'	2	EA		\$ -

Total :				\$	-
---------	--	--	--	----	---

Main Level O.S. Wall

Name	Qty	Units	Unit Price	Extended Price
1x2 PT x 10'	9	EA		\$ -
1x2 PT x 16'	28	EA		\$ -
1x2 PT x 8'	193	EA		\$ -
1x4 PT x 16'	42	EA		\$ -
4" Sill Seal x 25'	9	EA		\$ -

Total :				\$	-
---------	--	--	--	----	---

Main Level I.S. Walls

Name	Qty	Units	Unit Price	Extended Price
2x4 PT x 16'	16	EA		\$ -
2x4 SYP #2 x 10'	61	EA		\$ -
2x4 SYP #2 x 16'	63	EA		\$ -
2x4 SYP #2 x 8'	166	EA		\$ -
2x6 PT x 16'	1	EA		\$ -
2x6 SYP #2 x 16'	3	EA		\$ -
2x6 SYP #2 x 8'	10	EA		\$ -
4" Sill Seal x 25'	10	EA		\$ -
6 Sill Seal x 25'	1	EA		\$ -

Total :				\$	-
---------	--	--	--	----	---

Fascia And Soffit

Name	Qty	Units	Unit Price	Extended Price
2x4 SYP #2 x 16'	17	EA		\$ -
2x6 SYP #2 x 16'	17	EA		\$ -

Total :				\$	-
---------	--	--	--	----	---

Roof Sheathing

Name	Qty	Units	Unit Price	Extended Price
------	-----	-------	------------	----------------

19/32" CDX Plywood 4' x 8'	87	EA		\$	-
19/32" Sheathing Clips	2	Box(s)		\$	-
2x4 SYP #2 x 16'	28	EA		\$	-
2x6 SYP #2 x 16'	28	EA		\$	-
			Total :	\$	-

Roofing Load

Name	Qty	Units	Unit Price	Extended Price
30# Felt	15	Roll(s)		\$ -
30yr Architectural Shingles	87	BNDLS		\$ -
4' Off Ridge Vent	6	EA		\$ -
Coil Nails	2	Box(s)		\$ -
Drip Edge x 10'	26	EA		\$ -
Hip Shingles	6	Bundle(s)		\$ -
Ridge Shingles	2	Bundle(s)		\$ -
Staples	2	Box(s)		\$ -
Starter Shingles	3	BNDLS		\$ -
Valley Metal x 50'	2	Roll(s)		\$ -
			Total :	\$ -

Overhead Garage Door & Frames

Name	Qty	Units	Unit Price	Extended Price
16' x 7' Sectional Garage Door	1	EA		\$ -
			Total :	\$ -

Siding Materials

Name	Qty	Units	Unit Price	Extended Price
2x4 x 16'	16	EA		\$ -
2x6 x 16'	16	EA		\$ -
Fiber Cement/ Composite Soffit & Fascia Linear	235	FT		\$ -
Soffit TBD 16" x 12'	21	EA		\$ -
			Total :	\$ -

Insulation Load

Name	Qty	Units	Unit Price	Extended Price
3/4" R-4.1 Foil Insulation	1,789	SQ FT		\$ -
R-30 Blown Insulation	2,096	SQ FT		\$ -
			Total :	\$ -

Sheet Rock Load

Name	Qty	Units	Unit Price	Extended Price
1 1/4" Screws for Wood Studs 2500 Qty	5	Box(s)		\$ -
1 3/8" Drywall Nails 50 LB(s)	1	Box(s)		\$ -
1/2" Drywall 4' x 12'	118	EA		\$ -
1/2" MR Drywall 4' x 12'	16	EA		\$ -
1/2" Sag Resist Drywall 4' x 12'	28	EA		\$ -
All Purpose Pre-Mixed Joint Compound 4.5 Gal(s)	17	Pail(s)		\$ -
Drywall Adhesive - 29 oz. Tube	69	EA		\$ -
Drywall Joint Tape 2" x 250'	11	Roll(s)		\$ -
Paper-Faced Corner Bead 1 1/4" x 10' (50 Count)	5	Box(s)		\$ -
			Total :	\$ -

Trim Load

Name	Qty	Units	Unit Price	Extended Price
3-1/4" FJP Base	57	FT		\$ -
3-1/4" MDF Base	454	FT		\$ -
Window Sill	27	FT		\$ -
Total :				\$ -

Appliances

Name	Qty	Units	Unit Price	Extended Price
Dishwasher	1	EA		\$ -
Electric Dryer	1	EA		\$ -
Electric Range	1	EA		\$ -
Electric Water Heater	1	EA		\$ -
Refrigerator	1	EA		\$ -
Washer	1	EA		\$ -
Total :				\$ -

Plumbing Fixtures

Name	Qty	Units	Unit Price	Extended Price
2'6 Single sink vanity	1	EA		\$ -
2'9 Double Kitchen Sink	1	EA		\$ -
5'0 x 2'8 Tub/Shower	1	EA		\$ -
5'0 x 3'0 Shower	1	EA		\$ -
5'7 Double Sink Vanity	1	EA		\$ -
Hose Bib	2	EA		\$ -
Toilet	2	EA		\$ -
Total :				\$ -

Electrical Fixtures

Name	Qty	Units	Unit Price	Extended Price
1/2 Switched Outlet	1	EA		\$ -
2-Way Switch	24	EA		\$ -
220v Outlet	2	EA		\$ -
3-Way Switch	2	EA		\$ -
CO Detector	2	EA		\$ -
Ceiling Fan/Light	5	EA		\$ -
Ceiling Mount Light	5	EA		\$ -
Coax Terminal	5	EA		\$ -
Duplex Outlet	45	EA		\$ -
Exhaust Fan/Light Combo	2	EA		\$ -
Exterior Outlet	5	EA		\$ -
GFCI Outlet	3	EA		\$ -
Recessed Light	6	EA		\$ -
Shop Light	1	EA		\$ -
Smoke detector	7	EA		\$ -
Wall Light	5	EA		\$ -
Total :				\$ -

Flooring

Name	Qty	Units	Unit Price	Extended Price
Bed 2	152	SQ FT		\$ -
Bed 3	151	SQ FT		\$ -

Bed 4	152	SQ FT		\$	-
G Bath	42	SQ FT		\$	-
Hall	77	SQ FT		\$	-
Laundry	16	SQ FT		\$	-
Living Room/Kitchen/Dining	545	SQ FT		\$	-
Master Bath	44	SQ FT		\$	-
Master Suite	183	SQ FT		\$	-
WIC	67	SQ FT		\$	-
			Total :	\$	-

Interior Doors				
Name	Qty	Units	Unit Price	Extended Price
2468 LH	1	EA		\$ -
2668 LH	1	EA		\$ -
2668 Pocket	1	EA		\$ -
2868 LH	2	EA		\$ -
2868 RH	3	EA		\$ -
5468 Double Bi-Fold	1	EA		\$ -
6068 Double Bi-Fold	3	EA		\$ -
			Total :	\$ -

Windows				
Name	Qty	Units	Unit Price	Extended Price
1/2-23 SH Bot. Sash Temp	1	EA		\$ -
23 SH	1	EA		\$ -
25 SH	3	EA		\$ -
35 SH	2	EA		\$ -
			Total :	\$ -

Paint				
Name	Qty	Units	Unit Price	Extended Price
Painted Ceiling	1,912	SQ FT		\$ -
Painted Walls	5,297	SQ FT		\$ -
			Total :	\$ -

Exterior Door				
Name	Qty	Units	Unit Price	Extended Price
2868 RHOS 20min Fire Rated	1	EA		\$ -
3068 LHis	1	EA		\$ -
6068 OX SGD	1	EA		\$ -
			Total :	\$ -
			Sub Total:	\$ -
			Tax:	\$ -
			Bid Total:	\$ -

Type tax % in next cell---->