

Job Filename: OREILLY
Job Description: Untitled

Scale: 1":19.93'

Cross-section spacing: 0.50 FT

Soil Expansion: 0%
Soil Compression: 20%
Import Soil Compression: 20%

Cut Area: 7755.5 FT2
Fill Area: 37799.8 FT2
Work Area: 45626.5 FT2

Bank Cut: 120.2 YD3
Expanded Cut: 120.2 YD3
Bank Fill: 2238.2 YD3
Topsoil Stripped: 296.1 YD3
Topsoil Replaced: 204.4 YD3

Import: 2565.7 YD3
Topsoil Export: 91.7 YD3

EarthWorks Elements, Dimensions Report
Job Filename: OREILLY
Job Description: Untitled

Date: 02/17/21 Time: 03:00 PM

Please note that the following information is based solely on the areas' shape and depth and without regard to Perimeters and Excluded Areas.

| Area Name | Area, FT2 | Perimeter, FT |
|------------------------|-----------|---------------|
| BLDG | 7116.2 | 338.0 |
| Subtotal for Group: 15 | 7116.2 | 338.0 |

| Demolition Area Name | Area, FT2 | Perimeter, FT | Volume, YD3 |
|----------------------|-----------|---------------|-------------|
| PAVING TBR | 12586.0 | 722.0 | 233.1 |
| CONCRETE TBR | 837.4 | 334.0 | 15.5 |
| BLDG SLAB TBR | 4619.6 | 347.3 | 85.5 |

| Subgrade Name | Area, FT2 | Perimeter, FT | Volume, YD3 |
|-----------------------|-----------|---------------|-------------|
| LD PAVING | 996.5 | 139.8 | 27.7 |
| LD PAVING | 998.1 | 150.2 | 27.7 |
| LD PAVING | 2587.3 | 311.0 | 71.9 |
| Subtotal for Group: 1 | 4581.9 | 601.0 | 127.3 |

| | | | |
|-----------------------|---------|--------|-------|
| HD PAVING | 13146.6 | 1031.2 | 476.8 |
| Subtotal for Group: 3 | 13146.6 | 1031.2 | 476.8 |

| | | | |
|-----------------------|--------|-------|-------|
| HD CONC PAVING | 2092.1 | 254.1 | 77.5 |
| HD CONC PAVING | 794.3 | 119.7 | 29.4 |
| HD CONC PAVING | 190.2 | 55.2 | 7.0 |
| Subtotal for Group: 5 | 3076.6 | 428.9 | 113.9 |

| | | | |
|-----------------------|--------|-------|------|
| SIDEWALK | 1021.2 | 363.6 | 25.2 |
| Subtotal for Group: 9 | 1021.2 | 363.6 | 25.2 |

| | | | |
|------------------------|--------|-------|-------|
| BLDG | 7116.2 | 338.0 | 263.6 |
| Subtotal for Group: 15 | 7116.2 | 338.0 | 263.6 |

| Topsoil Area, Stripped | Area, FT2 | Perimeter, FT | Volume, YD3 |
|------------------------|-----------|---------------|-------------|
| TOPSOIL | 45630.0 | 864.5 | 0.0 |
| Topsoil Stripped #2 | 17435.8 | 787.2 | 215.3 |
| Topsoil Stripped #3 | 6544.2 | 372.9 | 80.8 |

Please note that the following information is based solely on the areas' shape and depth and without regard to Perimeters and Excluded Areas.

| | | | | |
|-----------------------|---------|-----------|----------|--|
| LD PAVING - None | | | | |
| HMA SURFACE | 1.50 in | 12.0 YD3 | 0.00 TON | |
| HMA BASE | 1.50 in | 12.0 YD3 | 0.00 TON | |
| AGG | 6.00 in | 47.9 YD3 | 0.00 TON | |
| LD PAVING - None | | | | |
| HMA SURFACE | 1.50 in | 4.6 YD3 | 0.00 TON | |
| HMA BASE | 1.50 in | 4.6 YD3 | 0.00 TON | |
| AGG | 6.00 in | 18.5 YD3 | 0.00 TON | |
| LD PAVING - None | | | | |
| HMA SURFACE | 1.50 in | 4.6 YD3 | 0.00 TON | |
| HMA BASE | 1.50 in | 4.6 YD3 | 0.00 TON | |
| AGG | 6.00 in | 18.5 YD3 | 0.00 TON | |
| HD PAVING - None | | | | |
| HMA SURFACE | 1.75 in | 71.0 YD3 | 0.00 TON | |
| HMA BASE | 2.00 in | 81.2 YD3 | 0.00 TON | |
| AGG | 8.00 in | 324.6 YD3 | 0.00 TON | |
| HD CONC PAVING - None | | | | |
| CONCRETE | 6.00 in | 38.7 YD3 | 0.00 TON | |
| BASE COURSE | 6.00 in | 38.7 YD3 | 0.00 TON | |
| HD CONC PAVING - None | | | | |
| CONCRETE | 6.00 in | 14.7 YD3 | 0.00 TON | |
| BASE COURSE | 6.00 in | 14.7 YD3 | 0.00 TON | |
| HD CONC PAVING - None | | | | |
| CONCRETE | 6.00 in | 3.5 YD3 | 0.00 TON | |
| BASE COURSE | 6.00 in | 3.5 YD3 | 0.00 TON | |
| SIDEWALK - None | | | | |
| SIDEWALK | 4.00 in | 12.6 YD3 | 0.00 TON | |
| BASE COURSE | 4.00 in | 12.6 YD3 | 0.00 TON | |
| BLDG - None | | | | |
| BLDG | 6.00 in | 131.8 YD3 | 0.00 TON | |
| BASE 304 | 6.00 in | 131.8 YD3 | 0.00 TON | |

EarthWorks Elements, Materials Summary Report Date: 02/17/21 Time: 03:00 PM
Job Filename: OREILLY
Job Description: Untitled

Please note that the following information is based solely on the areas' shape and depth and without regard to Perimeters and Excluded Areas.

Material totals in group 1

| | | |
|-------------|----------|----------|
| AGG | 84.8 YD3 | 0.00 TON |
| HMA BASE | 21.2 YD3 | 0.00 TON |
| HMA SURFACE | 21.2 YD3 | 0.00 TON |

Material totals in group 3

| | | |
|-------------|-----------|----------|
| AGG | 324.6 YD3 | 0.00 TON |
| HMA BASE | 81.2 YD3 | 0.00 TON |
| HMA SURFACE | 71.0 YD3 | 0.00 TON |

Material totals in group 5

| | | |
|-------------|----------|----------|
| BASE COURSE | 57.0 YD3 | 0.00 TON |
| CONCRETE | 57.0 YD3 | 0.00 TON |

Material totals in group 9

| | | |
|-------------|----------|----------|
| BASE COURSE | 12.6 YD3 | 0.00 TON |
| SIDEWALK | 12.6 YD3 | 0.00 TON |

Material totals in group 15

| | | |
|----------|-----------|----------|
| BASE 304 | 131.8 YD3 | 0.00 TON |
| BLDG | 131.8 YD3 | 0.00 TON |

Material totals by name

| | | |
|-------------|-----------|----------|
| AGG | 409.5 YD3 | 0.00 TON |
| BASE 304 | 131.8 YD3 | 0.00 TON |
| BASE COURSE | 69.6 YD3 | 0.00 TON |
| BLDG | 131.8 YD3 | 0.00 TON |
| CONCRETE | 57.0 YD3 | 0.00 TON |
| HMA BASE | 102.4 YD3 | 0.00 TON |
| HMA SURFACE | 92.2 YD3 | 0.00 TON |
| SIDEWALK | 12.6 YD3 | 0.00 TON |