

Item Description	Qty	Units	Color
<b>CLEARING &amp; SITE PREP</b>			
SAN MH TB RECONSTRUCTED	1	EA	Green
STORM STRUCTURE TBR	2	EA	Purple
SAN CLEANOUT TBR	1	EA	Yellow
ELEC STRUCTURE TBR	1	EA	Blue
POWER STRUCTURE TBR	2	EA	Red
SAWCUT	169	FT	Teal
STORM PIPE TBR	61	FT	Green
FD ASPHALT TBR, 6" THK.	12,662	SQ FT	Red
FD CONCRETE TBR, 6" THK.	858	SQ FT	Yellow
BLDG SLAB TBR, 6" THK.	4,659	SQ FT	Blue
<b>SOIL EROSION</b>			
CONCRETE WASHOUT	1	EA	Red
SILT FENCE	720	FT	Teal
EROSION CONTROL BLANKET	2,642	SQ FT	Yellow
RIP RAP	93	SQ FT	Green
CONSTRUCTION ENTRANCE	1,493	SQ FT	Blue
<b>EARTHWORK</b>			
TOPSOIL STRIP 4" THK.	296	CY	
BANK CUT	120	CY	
BANK FILL	2,238	CY	
IMPORT	2,565	CY	
ROUGH GRADE SITE	45,626	SF	
TOPSOIL REPLACED 4" THK	204	CY	
TOPSOIL EXPORT	91	CY	
<b>SANITARY</b>			
CONNECT TO SAN MH	1	EA	Red
CLEANOUT	3	EA	Green
6" PVC-IN PAVING	333	FT	Green
<b>STORM</b>			
12" STORM PIPE, 0-8' DP.-IN PAVING	98	FT	Cyan
12" FLARED END SECTION	4	EA	Yellow
<b>WATER</b>			
CONNECT TO EX. WATERMAIN	1	EA	Blue
5/8" IRRIG. METER	1	EA	Purple
5/8" RPZ	1	EA	Teal
5/8" PLUG	1	EA	Red
1" TAPPING SLEEVE	1	EA	Green
IRRIG. PIPE	17	FT	Blue
1.5" DOMESTIC SERVICE-IN PAVING	336	FT	Yellow
SAWCUT	79	FT	Yellow
TRENCH REPAIR STRIP	39	FT	Cyan
<b>CURB &amp; PAVEMENT</b>			
BARRIER CURB	682	FT	Blue
TRANSITION CURB	59	FT	Purple
HD PAVING, 8" AGG/2" HMA BASE/1.75" HMA SURFACE	13,111	SQ FT	Cyan
HD CONCRETE PAVING 6" THK. W/6" BASE COURSE	3,186	SQ FT	Green
LD PAVING, 6" AGG/ 1.5" HMA/1.5" HMA SURFACE	4,580	SQ FT	Red
CONCRETE SIDEWALK 5" THK. W/6" BASE COURSE	1,084	SQ FT	Green