

Job Filename: PUBLIX SITE
Job Description: Untitled

Scale: 1":20.31'

Cross-section spacing: 1.00 FT

Soil Expansion: 0%
Soil Compression: 0%
Import Soil Compression: 0%

Cut Area: 59624.0 FT2
Fill Area: 545463.0 FT2
Work Area: 605087.0 FT2

Bank Cut:	4047.6 YD3
Expanded Cut:	4047.6 YD3
Bank Fill:	38660.9 YD3
Topsoil Stripped:	11199.1 YD3
Topsoil Replaced:	3308.0 YD3

Import:	34613.4 YD3
Topsoil Export:	7891.1 YD3

Please note that the following information is based solely on the areas' shape and depth and without regard to Perimeters and Excluded Areas.

Area Name	Area, FT2	Perimeter, FT
BLDG	60481.9	1326.2
Subtotal for Group: 107	60481.9	1326.2

Subgrade Name	Area, FT2	Perimeter, FT	Volume, YD3
HD PAVING	6168.7	573.6	199.9
HD PAVING	9198.6	712.9	298.1
HD PAVING	8677.2	728.9	281.2
HD PAVING	24017.4	1996.3	778.3
HD PAVING	35389.2	2297.3	1146.9
HD PAVING	13015.6	1154.7	421.8
HD PAVING	10644.1	742.6	344.9
Subtotal for Group: 1	107110.9	8206.4	3471.2

LD PAVING	17768.5	995.0	548.4
LD PAVING	10680.7	848.3	329.7
LD PAVING	32539.3	1395.3	1004.3
LD PAVING	3936.4	473.6	121.5
LD PAVING	12303.1	994.7	379.7
LD PAVING	36976.9	1668.4	1141.3
LD PAVING	37759.5	2134.6	1165.4
Subtotal for Group: 3	151964.4	8509.9	4690.3

CONC COMP PAD	1150.5	137.6	21.3
Subtotal for Group: 5	1150.5	137.6	21.3

SIDEWALK	146.9	61.1	1.8
SIDEWALK	3157.5	579.1	39.0
SIDEWALK	1910.1	456.3	23.6
SIDEWALK	278.5	119.5	3.4
SIDEWALK	99.4	51.4	1.2
SIDEWALK	71.9	44.9	0.9
SIDEWALK	1112.0	345.9	13.7
SIDEWALK	1011.1	346.0	12.5
SIDEWALK	310.1	124.1	3.8
SIDEWALK	358.9	132.0	4.4
SIDEWALK	3142.5	1148.6	38.8
SIDEWALK	281.2	103.7	5.2
SIDEWALK	241.5	91.6	3.0
SIDEWALK	245.7	88.1	3.0
SIDEWALK	231.0	87.3	2.9
SIDEWALK	226.3	87.2	2.8
SIDEWALK	215.6	86.2	2.7
SIDEWALK	76.3	46.2	0.9

Subgrade Name	Area, FT2	Perimeter, FT	Volume, YD3
SIDEWALK	73.6	45.1	0.9
SIDEWALK	75.7	45.6	0.9
SIDEWALK	77.4	45.6	1.0
SIDEWALK	74.1	46.1	0.9
SIDEWALK	620.9	245.2	7.7
Subtotal for Group: 7	14038.2	4426.9	175.0
LOADING DOCK	1032.7	135.5	19.1
LOADING DOCK	2110.3	201.8	39.1
Subtotal for Group: 9	3143.0	337.3	58.2
CONC DUMPSTER PAD	312.5	75.5	5.8
Subtotal for Group: 101	312.5	75.5	5.8
BLDG	60481.9	1326.2	1120.0
Subtotal for Group: 107	60481.9	1326.2	1120.0
Topsoil Area, Stripped	Area, FT2	Perimeter, FT	Volume, YD3
TOPSOIL	605107.8	6925.4	11205.7

Please note that the following information is based solely on the areas' shape and depth and without regard to Perimeters and Excluded Areas.

HD PAVING - None				
SURFACE	1.00 in	109.2 YD3	0.00 TON	
STRUCTURAL	1.50 in	163.8 YD3	0.00 TON	
LIMEROCK	8.00 in	873.8 YD3	0.00 TON	
HD PAVING - None				
SURFACE	1.00 in	74.1 YD3	0.00 TON	
STRUCTURAL	1.50 in	111.2 YD3	0.00 TON	
LIMEROCK	8.00 in	593.0 YD3	0.00 TON	
HD PAVING - None				
SURFACE	1.00 in	40.2 YD3	0.00 TON	
STRUCTURAL	1.50 in	60.3 YD3	0.00 TON	
LIMEROCK	8.00 in	321.4 YD3	0.00 TON	
HD PAVING - None				
SURFACE	1.00 in	19.0 YD3	0.00 TON	
STRUCTURAL	1.50 in	28.6 YD3	0.00 TON	
LIMEROCK	8.00 in	152.3 YD3	0.00 TON	
HD PAVING - None				
SURFACE	1.00 in	28.4 YD3	0.00 TON	
STRUCTURAL	1.50 in	42.6 YD3	0.00 TON	
LIMEROCK	8.00 in	227.1 YD3	0.00 TON	
HD PAVING - None				
SURFACE	1.00 in	32.9 YD3	0.00 TON	
STRUCTURAL	1.50 in	49.3 YD3	0.00 TON	
LIMEROCK	8.00 in	262.8 YD3	0.00 TON	
HD PAVING - None				
SURFACE	1.00 in	26.8 YD3	0.00 TON	
STRUCTURAL	1.50 in	40.2 YD3	0.00 TON	
LIMEROCK	8.00 in	214.3 YD3	0.00 TON	
LD PAVING - None				
SURFACE	2.00 in	65.9 YD3	0.00 TON	
LIMEROCK	8.00 in	263.7 YD3	0.00 TON	
LD PAVING - None				
SURFACE	2.00 in	109.7 YD3	0.00 TON	
LIMEROCK	8.00 in	438.7 YD3	0.00 TON	
LD PAVING - None				
SURFACE	2.00 in	75.9 YD3	0.00 TON	
LIMEROCK	8.00 in	303.8 YD3	0.00 TON	

LD PAVING - None			
SURFACE	2.00 in	24.3 YD3	0.00 TON
LIMEROCK	8.00 in	97.2 YD3	0.00 TON
LD PAVING - None			
SURFACE	2.00 in	200.9 YD3	0.00 TON
LIMEROCK	8.00 in	803.4 YD3	0.00 TON
LD PAVING - None			
SURFACE	2.00 in	228.3 YD3	0.00 TON
LIMEROCK	8.00 in	913.0 YD3	0.00 TON
LD PAVING - None			
SURFACE	2.00 in	233.1 YD3	0.00 TON
LIMEROCK	8.00 in	932.3 YD3	0.00 TON
CONC COMP PAD - None			
CONCRETE	6.00 in	21.3 YD3	0.00 TON
SIDEWALK - None			
SIDEWALK	6.00 in	5.2 YD3	0.00 TON
SIDEWALK - None			
SIDEWALK	4.00 in	13.7 YD3	0.00 TON
SIDEWALK - None			
SIDEWALK	4.00 in	1.8 YD3	0.00 TON
SIDEWALK - None			
SIDEWALK	4.00 in	4.4 YD3	0.00 TON
SIDEWALK - None			
SIDEWALK	4.00 in	39.0 YD3	0.00 TON
SIDEWALK - None			
SIDEWALK	4.00 in	3.8 YD3	0.00 TON
SIDEWALK - None			
SIDEWALK	4.00 in	3.4 YD3	0.00 TON
SIDEWALK - None			
SIDEWALK	4.00 in	23.6 YD3	0.00 TON
SIDEWALK - None			
SIDEWALK	4.00 in	1.2 YD3	0.00 TON
SIDEWALK - None			
SIDEWALK	4.00 in	0.9 YD3	0.00 TON
SIDEWALK - None			
SIDEWALK	4.00 in	0.9 YD3	0.00 TON

SIDEWALK - None SIDEWALK	4.00 in	12.5 YD3	0.00 TON
SIDEWALK - None SIDEWALK	4.00 in	38.8 YD3	0.00 TON
SIDEWALK - None SIDEWALK	4.00 in	3.0 YD3	0.00 TON
SIDEWALK - None SIDEWALK	4.00 in	3.0 YD3	0.00 TON
SIDEWALK - None SIDEWALK	4.00 in	2.9 YD3	0.00 TON
SIDEWALK - None SIDEWALK	4.00 in	2.8 YD3	0.00 TON
SIDEWALK - None SIDEWALK	4.00 in	2.7 YD3	0.00 TON
SIDEWALK - None SIDEWALK	4.00 in	0.9 YD3	0.00 TON
SIDEWALK - None SIDEWALK	4.00 in	0.9 YD3	0.00 TON
SIDEWALK - None SIDEWALK	4.00 in	0.9 YD3	0.00 TON
SIDEWALK - None SIDEWALK	4.00 in	1.0 YD3	0.00 TON
SIDEWALK - None SIDEWALK	4.00 in	7.7 YD3	0.00 TON
LOADING DOCK - None LOADING DOCK	6.00 in	39.1 YD3	0.00 TON
LOADING DOCK - None LOADING DOCK	6.00 in	19.1 YD3	0.00 TON
CONC DUMPSTER PAD - None CONCRETE DUMPSTER PAD	6.00 in	5.8 YD3	0.00 TON
BLDG - None BLDG	6.00 in	1120.0 YD3	0.00 TON

EarthWorks Elements, Materials Summary Report Date: 10/04/21 Time: 02:34 PM
Job Filename: PUBLIX SITE
Job Description: Untitled

Please note that the following information is based solely on the areas' shape and depth and without regard to Perimeters and Excluded Areas.

Material totals in group 1

LIMEROCK	2644.7 YD3	0.00 TON
STRUCTURAL	495.9 YD3	0.00 TON
SURFACE	330.6 YD3	0.00 TON

Material totals in group 3

LIMEROCK	3752.2 YD3	0.00 TON
SURFACE	938.1 YD3	0.00 TON

Material totals in group 5

CONCRETE	21.3 YD3	0.00 TON
----------	----------	----------

Material totals in group 7

SIDEWALK	175.0 YD3	0.00 TON
----------	-----------	----------

Material totals in group 9

LOADING DOCK	58.2 YD3	0.00 TON
--------------	----------	----------

Material totals in group 101

CONCRETE DUMPSTER PAD	5.8 YD3	0.00 TON
-----------------------	---------	----------

Material totals in group 107

BLDG	1120.0 YD3	0.00 TON
------	------------	----------

Material totals by name

BLDG	1120.0 YD3	0.00 TON
CONCRETE	21.3 YD3	0.00 TON
CONCRETE DUMPSTER PAD	5.8 YD3	0.00 TON
LIMEROCK	6396.9 YD3	0.00 TON
LOADING DOCK	58.2 YD3	0.00 TON
SIDEWALK	175.0 YD3	0.00 TON
STRUCTURAL	495.9 YD3	0.00 TON
SURFACE	1268.6 YD3	0.00 TON