Name

FOUNDATION

FTG-20 FOOTING 2'W 1'D 3#5 BOTTTOM #5 TRANS 16"OC
F 3025X3.5 FOOTING 3'3"X3'6"X1' D 4 #5 SHORT 4#5 LONG
F5.5X5.5 FOOTING 5'5X5'5X1'D W/6#5 EACH WAY
F4.0X4.0 FOOTING 4'X4'X1'D W/5#5 EW
F4.0X5.0 FOOTING W/4'X4'X1'D W/6#5 SHORT 5 #5 LONG
8"X48" L DOWEL
SOG-4 4"D SLAB W/6X6 W1.4XW1.4 WWM
4"D PERIMETER SLAB W/6X6 W1.4XW1.4 WWM
12"W 8"D SLAB EDGE W/3#4 CONT W/9"X16" L-DOWEL 32"OC
#4 REBAR 4'
SLAB CONTROL JOINTS L/F

SIDEWALK

4" SIDEWALK W/6X6 W1.4XW1.4 WWM
DUMPSTER PAD SLAB

CONCRETE BLOCK WALL

23'4" CONCRETE BLOCK WALL #5 16"OC VERT 1#5 HORIZ T&B #5 HORIZ 48"OC 9GA LADDER 16"OC
21'4-1/2" CONCRETE BLOCK WALL #5 16"OC VERT 1#5 T&B 1#5 HORIZ 48"OC 9GA LATTER 16"OC
17'3-1/2" CONCRETE BLOCK WALL #5 16"OC VERT 1 #5 HORIZ T&B 1#5 HORIZ 48"OC 9GA LADER 16"OC
20'7 CONCRETE BLOCK WALL #5 16"OC 1#5 HORIZ T&B 1#5 INT 9GA LADDER 16"OC
26'2" CONCRETE BLOCK WALL #5 16"OC VERT 1 #5 HORIZ T&B 1 #5 48"OC 9GA LADDER 16"OC
8X8X8 CONCRETE CORNER BLOCK
L1 LINTEL W/2 #5 BOTTOM
L2 LINTEL8 8"LINTEL BLOCK W/8" KNOCKOUT BLOCK 2 #5 T*B
#5 48"X48" L CORNER
PEDESTAL PIER P1 32"X32"X3'8"T W/8#5 #5 CLOSED TIES 6"OC
PEDESTAL PIER P3 26"X19"X3'8"T W/4#5 EACH CORNER #4 CLOSED TIE 6"OC
PEDESTAL PIER P2 32"X44" X3'8"TW/8#5 #4 CLOSED TIE 6"OC

STUCCO

STUCCO

BRICK

BRICK
CONTROL JOINTS AT BRICK
12" MORTAR NET
L5X5X3/8 STEEL LINTEL

PRECAST STONE

8"X32" PRECAST STONE SEGMENT

Name

8"X12" PRECAST STONE SEGMENT

8"X14" PRECAST STONE SEGMENT

6"X32" PRECAST STONE SEGMENT

6"X12" PRECAST STONE SEGMENT

20"X32" PRECAST STONE PARAPET CAP SEGMENT

6"X14" PRECAST STONE SEGMENT

Labor Total

Qty	Units	Color	Labor Cost	Extended
517.3	FT		$ -	$ -
68.27	SQ FT		$ -	$ -
146.7	SQ FT		$ -	$ -
96	SQ FT		$ -	$ -
40	SQ FT		$ -	$ -
258.95	FT		$ -	$ -
3727.94	SQ FT		$ -	$ -
1044.85	SQ FT		$ -	$ -
394.75	FT		$ -	$ -
36	EA		$ -	$ -
439.36	FT		$ -	$ -
5390.47	SQ FT		$ -	$ -
414.56	SQ FT		$ -	$ -
46.5	FT		$ -	$ -
94.09	FT		$ -	$ -
8	FT		$ -	$ -
64.5	FT		$ -	$ -
64.75	FT		$ -	$ -
234	EA		$ -	$ -
24.5	FT		$ -	$ -
32.25	FT		$ -	$ -
128	EA		$ -	$ -
14.22	SQ FT		$ -	$ -
20.58	SQ FT		$ -	$ -
19.56	SQ FT		$ -	$ -
4720.6	SQ FT		$ -	$ -
3852.56	SQ FT		$ -	$ -
203.43	FT		$ -	$ -
206.71	FT		$ -	$ -
58	FT		$ -	$ -
42	EA		$ -	$ -

Qty	Units	Color	Labor Cost	Extended
27	EA		$ -	$ -
38	EA		$ -	$ -
13	EA		$ -	$ -
35	EA		$ -	$ -
14	EA		$ -	$ -
24	EA		$ -	$ -
				$ -