Item Name	Location
FOUNDATION	
CONCRETE	
3000 PSI CONCRETE	FOOTING
3000 PSI CONCRETE	SLAB
3000 PSI CONCRETE	PERIMETER SLAB
3000 PSI CONCRETE	THICKENED SLAB
3000 PSI CONCRETE	SIDEWALK
3000 PSI CONCRETE	DUMPSTER PAD
3000 PSI CONCRETE	LINTELS
3000 PSI CONCRETE	PEDESTALS
	TOTAL 3000 PSI

CONCRETE BLOCK WALL CELL FILL

2000 PSI CONCRETE

FOOTING STEEL

#5 REBAR 20'
3 BAR CHAIRS
2 BAR CHAIRS
#4 L DOWEL 8"X48"

SLAB STEEL

7.5'X20' 6X6 W1.4XW1.4 WELDED WIRE MESH
MESH CHAIRS
VISQUEEN 20X100
VISQUEEN TAPE
#4 REBAR 4'
SLAB CONTROL JOINT

PERIMETER SLAB STEEL

7.5'X20' 6X6 W1.4XW1.4 WELDED WIRE MESH
MESH CHAIRS
VISQUEEN 20X100
VISQUEEN TAPE

THICKEND SLAB STEEL

#4 REBAR 20'
2 BAR CHAIRS

Item Name **Location**

SIDEWALK STEEL

7.5'X20' 6X6 W1.4XW1.4 WELDED WIRE MESH
MESH CHAIRS
VISQUEEN 20X100
VISQUEEN TAPE

DUMPSTER PAD SLAB STEEL

7.5'X20' 6X6 W1.4XW1.4 WELDED WIRE MESH
MESH CHAIRS

23'4" CONCRETE BLOCK WALL #5 16"OC VERT 1#5 HORIZ T&B #5 HORIZ 48"OC 9GA LADDER 16"OC

8X16 CONCRETE BLOCK
4X8X16 CONCRETE BLOCK
MORTAR (70LB BAG)
SAND (TON)
#5 REBAR 20'
8"X8' 9GA LADDER

21'4-1/2" CONCRETE BLOCK WALL #5 16"OC VERT 1#5 T&B 1#5 HORIZ 48"OC 9GA LATTER 16"OC

8X16 CONCRETE BLOCK
MORTAR (70LB BAG)
SAND (TON)
#5 REBAR 20'
8"X8' 9GA LADDER

17'3-1/2" CONCRETE BLOCK WALL #5 16"OC VERT 1 #5 HORIZ T&B 1#5 HORIZ 48"OC 9GA LADER 16"OC

8X16 CONCRETE BLOCK
MORTAR (70LB BAG)
SAND (TON)
#5 REBAR 20'
8"X8' 9GA LADDER

20'7 CONCRETE BLOCK WALL #5 16"OC 1#5 HORIZ T&B 1#5 INT 9GA LADDER 16"OC

Item Name	Location
8X16 CONCRETE BLOCK	
4X8X16 CONCRETE BLOCK	
MORTAR (70LB BAG)	
SAND (TON)	
#5 REBAR 20'	
8"X8' 9GA LADDER	

26'2" CONCRETE BLOCK WALL #5 16"OC VERT 1 #5 HORIZ T&B 1 #5 48"OC 9GA LADDER 16"OC

8X16 CONCRETE BLOCK
MORTAR (70LB BAG)
SAND (TON)
#5 REBAR 20'
8"X8' 9GA LADDER
#5 48"X48" L CORNER

CORNER BLOCKS

8X8X8 CONCRETE CORNER BLOCK

LINTELS

L1 LINTEL W/2 #5 BOTTOM @ 3.5'
8"X3'6 LINTEL BLOCK
#5 REBAR 20'

L2 LINTEL8 8"LINTEL BLOCK W/8" KNOCKOUT BLOCK 2 #5 T*B

8"X11' LINTEL BLOCK
8"X16" KNOCKOUT BLOCK
#5 REBAR 20'

PEDESTAL PIER STEEL

#5 REBAR 20'
#4 CLOSED TIE W/INT TIE FOR 32X32 PIER
#4 CLOSED TIE W/INT TIE FOR 26"X19" PIER
#4 CLOSED TIE W/INT TIE FOR 32X44 PIER

STUCCO

3 COAT HARDCOAT STUCCO

Item Name	Location
BRICK	
Modular Brick	
Brick Mortar	
SAND (TON)	
BRICK TIES	
CONTROL JOINTS AT BRICK	
12" MORTAR NET	
L5X5X3/8 STEEL LINTELS	
L5X5X3/8 STEEL LINTEL @ 4'	
L5X5X3/8 STEEL LINTEL @ 10'	
PRECAST STONE	
8"X32" PRECAST STONE SEGMENT	
8"X12" PRECAST STONE SEGMENT	
8"X14" PRECAST STONE SEGMENT	
6"X32" PRECAST STONE SEGMENT	
6"X12" PRECAST STONE SEGMENT	
20"X32" PRECAST STONE PARAPET CAP SEGMENT	
6"X14" PRECAST STONE SEGMENT	

Qty	Units	Unit Price	Extended
54	CU YD	$ -	$ -
49	CU YD		$ -
14	CU YD		$ -
11	CU YD		$ -
70	CU YD		$ -
6	CU YD		$ -
2	CU YD		$ -
9	CU YD		$ -
215	**CU YD**		
83	CU YD		$ -
269	EA		$ -
197	EA		$ -
36	EA		$ -
107	EA		$ -
28	Sheet(s)		$ -
586	EA		$ -
3	Roll(s)		$ -
5	Roll(s)		$ -
36	EA		$ -
484	FT		$ -
8	Sheet(s)		$ -
165	EA		$ -
1	Roll(s)		$ -
2	Roll(s)		$ -
82	EA		$ -
109	EA		$ -

Qty	Units	Unit Price	Extended
40	Sheet(s)		$ -
848	EA		$ -
3	Roll(s)		$ -
6	Roll(s)		$ -
4	Sheet(s)		$ -
66	EA		$ -
1283	EA		$ -
36	EA		$ -
56	Bag(s)		$ -
5	EA		$ -
97	EA		$ -
122	EA		$ -
2390	EA		$ -
104	Bag(s)		$ -
9	EA		$ -
195	EA		$ -
233	EA		$ -
167	EA		$ -
8	Bag(s)		$ -
1	EA		$ -
18	EA		$ -
16	EA		$ -

Qty	Units	Unit Price	Extended
1575	EA		$ -
50	EA		$ -
68	Bag(s)		$ -
6	EA		$ -
134	EA		$ -
151	EA		$ -
2008	EA		$ -
88	Bag(s)		$ -
7	EA		$ -
134	EA		$ -
187	EA		$ -
128	EA		$ -
234	EA		$ -
7	EA		$ -
7	EA		$ -
6	EA		$ -
3	EA		$ -
30	EA		$ -
9	EA		$ -
30	EA		$ -
9	EA		$ -
9	EA		$ -
9	EA		$ -
5193	SQ FT		$ -

Qty	Units	Unit Price	Extended
26630	EA		$ -
236	Bag(s)		$ -
28	EA		$ -
2224	EA		$ -
224	FT		$ -
228	FT		$ -
7	EA		$ -
3	EA		$ -
42	EA		$ -
27	EA		$ -
38	EA		$ -
13	EA		$ -
35	EA		$ -
14	EA		$ -
24	EA		$ -