



## Materials By Location

### Quick Trip #4068 Convenient Store & Gas Pumps

#### Concrete

##### Concrete Pavement

Name	Description	Qty	Units
#3 Rebar x 1'	Deformed Tie bars	137	EA
#3 Rebar x 20'	Concrete Pavement	5624	EA
#3 Rebar x 20'	Pavement	44	EA
#3 Rebar x 20'	Side Store	70	EA
#3 Rebar x 4'	Deformed Tie bars @6"	9	EA
#4 Rebar x 1'	Tied Joint Dowel	14	EA
#5 Rebar x 4'	Deformed Tie bars @6"	5	EA
1" Dia. x 1.5'	Curb & Gutter	1148	EA
1" Dia. x 1.5'	Pavement	7321	EA
1/2" Dia. x 1'	Pavement @Bollards	577	EA
12" Dia. x 2.17' Sonotube Forms	Concrete Encasement	38	EA
24" Dia. x 3.5' Sonotube Forms	Concrete Embedment	50	EA
4000 PSI Concrete	Concrete Embedment	21	CU YD
4000 PSI Concrete	Concrete Encasement	3	CU YD
4000 PSI Concrete	Concrete Pavement	1944	CU YD
4000 PSI Concrete	Curb	50	CU YD
4000 PSI Concrete	Curb & Gutter	22	CU YD
4000 PSI Concrete	Pavement	18	CU YD
4000 PSI Concrete	Side Store	25	CU YD
Footing Forms	Curb	3210	SQ FT
Single Rebar Chairs	Concrete Pavement	22491	EA
Single Rebar Chairs	Pavement	173	EA
Single Rebar Chairs	Side Store	279	EA
Slab Perimeter Forms	Concrete Pavement	4803	SQ FT
Slab Perimeter Forms	Curb & Gutter	364	SQ FT
Slab Perimeter Forms	Pavement	388	SQ FT
Slab Perimeter Forms	Side Store	532	SQ FT

##### Footings

Name	Description	Qty	Units
------	-------------	-----	-------

#3 Rebar 2' x 4'	Rebar Pre-Bent Dowels	18	EA
#3 Rebar x 20"	8' Blockout	13	EA
#3 Rebar x 20"	Continuous Footings	150	EA
#3 Rebar x 32"	Continuous Footings	11	EA
#4 Rebar Stirrups 44" Dia.	7' Canopy Round Footings	52	EA
#4 Rebar Stirrups 50" Dia.	6'-6" Canopy Round	21	EA
#5 Rebar 1.5' x 2'	Rebar Pre-Bent Dowels	20	EA
#5 Rebar 2' x 2'	Rebar Pre-Bent Dowels	20	EA
#5 Rebar x 3.5'	Rebar Straight Dowels	8	EA
#5 Rebar x 4'	Rebar Straight Dowels Point	13	EA
#5 Rebar x 4'	Side Entry	13	EA
#5 Rebar x 4.5'	Rebar Straight Dowels	72	EA
#5 Rebar x 6'	Blockout A	72	EA
#5 Rebar x 7'	Blockout B	5	EA
#6 Rebar x 20'	8' Blockout	7	EA
#6 Rebar x 20'	Continuous Footings	83	EA
#6 Rebar x 56"	Canopy Square Footings	210	EA
#8 Rebar x 7'	6'-6" Canopy Round	51	EA
#8 Rebar x 7'	7' Canopy Round Footings	89	EA
4000 PSI Concrete	6'-6" Canopy Round	13	CU YD
4000 PSI Concrete	7' Canopy Round Footings	24	CU YD
4000 PSI Concrete	8' Blockout	4	CU YD
4000 PSI Concrete	Canopy Square Footings	54	CU YD
4000 PSI Concrete	Continuous Footings	45	CU YD
48" Dia. x 7' Sonotube Forms	7' Canopy Round Footings	8	EA
54" Dia. x 6.5' Sonotube Forms	6'-6" Canopy Round	4	EA
Footing Forms	Continuous Footings	82	SQ FT
Spread Footings Forms	Canopy Square Footings	1155	SQ FT
Wall Footing Forms	8' Blockout	101	SQ FT
Wall Footing Forms	Continuous Footings	1180	SQ FT
Wood Stakes x 18"	Continuous Footings	68	EA

### Foundation Slabs

Name	Description	Qty	Units
10 Mil Polyethelene	SOG	6	EA
4000 PSI Concrete	SOG	63	CU YD
6x6 - w1.4 x w1.4 6x6 - w1.4 x w1.4	SOG	34	EA
Sand	SOG	82	Ton(s)
Slab Perimeter Forms	SOG	313	SQ FT
Washed Gravel	SOG	85	Ton(s)

### Sidewalks

Name	Description	Qty	Units
4000 PSI Concrete	Concrete Pavement	38	CU YD
6x6 10 Ga. W.W.F. 6x6 10 Ga. W.W.F.	Concrete Pavement	17	EA
Slab Perimeter Forms	Concrete Pavement	568	SQ FT
Underslab Forms	Concrete Pavement	27	SQ FT

